

## Corrigendum No. 1

### e - TENDER NOTICE NO. 01 FOR 2013-14. System Generated No. 225

Following changes are made as mentioned below

Seq No	VIDC Stage	Vender Stage	Start Date & Time	Expiry Date & Time	New start date and time	New Expiry date & time
1	Release Tender	-	21.11.2013 10.00	25.11.2013 10.00	<b>21.11.2013 10.00</b>	<b>25.11.2013 10.00</b>
2	-	Tender Document sale/download	25.11.2013 10.01	20.12.2013 18.00	<b>25.11.2013 10.01</b>	<b>6.1.2014 18.00</b>
3	-	Pre Tender Conference	13.12.2013		<b>27/12/2013</b>	
4		Tender Document Preparation and Submission -	25.11.2013 10.00	20.12.2013 18.00	<b>25.12.2013 10.00</b>	<b>6.1.2014 18.00</b>
5	Close for Technical bid	-	21.12.2013 10.00	21.12.2013 18.00	<b>7.1.2014 10.00</b>	<b>7.1.2014 18.00</b>
6	Close for price bid		21.12.2013 10.00	21.12.2013 18.00	<b>7.1.2014 10.00</b>	<b>7.1.2014 18.00</b>
7		Tender Document Resubmission (Re-encryption)	21.12.2013 18.01	24.12.2013 18.00	<b>7.1.2014 18.01</b>	<b>10.1.2014 18.00</b>
8	Technical bid opening	-	25.12.2013 10.00	26.12.2013 18.00	<b>13.1.2014 10.00</b>	<b>14.1.2014 18.00</b>
9	Price bid opening	-	25.12.2013 10.00	26.12.2013 18.00	<b>13.1.2014 10.00</b>	<b>14.1.2014 18.00</b>

#### Schedule "A"

Old	New
Nil	<b>3232 Bag</b>
Nil	<b>16.547 Mt</b>
Nil	<b>10 Rmt</b>

#### Schedule "B"

Old	New
<b>Item No.3:-</b> Providing soling using 80 mm size / granite / quartzite / gneiss /	<b>Item No.3:-</b> Providing soling using 80 mm size / granite / quartzite / gneiss /

<p>trap metal in 15cm layer, including hand packing, filling voids with sand / grit,ramming,watering With contractors own material, including all leads &amp; lifts etc. complete</p>	<p>trap metal in 15cm layer, including hand packing, filling voids with sand / grit,ramming,watering With contractors own material, including all leads &amp; lifts etc. complete <b>including royalty charges.</b></p>
<p><b>Item No.4-</b> Providing and filling sand below raft and in box return including compaction. As directed by Engineer in-charge. With contractors own material, Including all leads &amp; lifts etc. complete.</p>	<p><b>Item No.4-</b> Providing and filling sand below raft and in box return including compaction. As directed by Engineer in-charge. With contractors own material, Including all leads &amp; lifts etc. complete. <b>including royalty charges.</b></p>
<p><b>Item No.5:-</b>Providing and laying in situ M-10 / 1:3:6 cement concrete of trap / granite / quartzite / gneiss metal for leveling course below R.C.C. Raft and foundation, including necessary plywood / steel formwork and steel centering, compaction by vibrator, finishing curing etc, complete. The C.M.1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc.( Wooden centering / formwork will not be allowed.) With contractors own material, including all leads &amp; lifts etc, complete. rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bags, plastic, tarpaulin etc.( wooden centering / formwork will not be allowed.) with all lead and lift and as directed by Engineer in charge etc complete M-10 ( 40 MSA)</p>	<p><b>Item No.5:-</b>Providing and laying in situ M-10 / 1:3:6 cement concrete of trap / granite / quartzite / gneiss metal for leveling course below R.C.C. Raft and foundation, including necessary plywood / steel formwork and steel centering, compaction by vibrator, finishing curing etc, complete. The C.M.1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc.( Wooden centering / formwork will not be allowed.) With contractors own material, including all leads &amp; lifts etc, complete. rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bags, plastic, tarpaulin etc.( wooden centering / formwork will not be allowed.) with all lead and lift and as directed by Engineer in charge etc complete M-10 ( 40 MSA) <b>with contractor own material including royalty charges.</b></p>
<p><b>Item No.6:-</b>Providing and laying in situ c.c. of required grade of trap / granite / quartzite / gneiss metal for cut-off and curtain wall, including plywood / steel formwork and steel centering, compaction by vibrator, finishing uneven and honeycombed surface with C.M.-1:3 of sufficient minimum thickness to give a smooth and even surface or roughening the surface if special finish is to be provided, curing etc. complete.( Excluding reinforcement, including cover block.) The C.M.-1:3 plaster is considered for rendering uneven and honeycombed surface only.( Excluding</p>	<p><b>Item No.6:-</b>Providing and laying in situ c.c. of required grade of trap / granite / quartzite / gneiss metal for cut-off and curtain wall, including plywood / steel formwork and steel centering, compaction by vibrator, finishing uneven and honeycombed surface with C.M.-1:3 of sufficient minimum thickness to give a smooth and even surface or roughening the surface if special finish is to be provided, curing etc. complete.( Excluding reinforcement, including cover block.) The C.M.-1:3 plaster is considered for rendering uneven and honeycombed surface only.( Excluding</p>

<p>cost of reinforcement ) Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc.( Wooden centering / formwork will not be allowed.) With contractors own material, including all leads &amp; lifts etc. complete.. C.C.-M-15 (20 MSA)</p>	<p>cost of reinforcement ) Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc.( Wooden centering / formwork will not be allowed.) With contractors own material, including all leads &amp; lifts etc. complete.. C.C.-M-15 (20 MSA) including royalty charges.</p>
<p><b>Item No.7:-</b>Providing and laying cement concrete of required grade of trap / granite / quartzite / gneiss metal for cast in situ piers, abutments, returns wings, Face wall etc. including provision of "V" shaped false joints to form suitable panels on the faces to approved design, including plywood / steel formwork and steel centering, compaction by vibrator, finishing uneven and honeycombed surface with C.M.-1:3 of sufficient minimum thickness to give a smooth and even surface, or roughening the surface if special finish is to be provided, curing and bailing out water. The C.M. 1:3 plaster is considered for rendering uneven and honeycombed surface only.( Excluding reinforcement, including cover block.) Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc.( Wooden centering / formwork will not be allowed.) With contractors own material, including all leads &amp; lifts etc. complete. C.C.-M-15 (40 MSA)</p>	<p><b>Item No.7:-</b>Providing and laying cement concrete of required grade of trap / granite / quartzite / gneiss metal for cast in situ piers, abutments, returns wings, Face wall etc. including provision of "V" shaped false joints to form suitable panels on the faces to approved design, including plywood / steel formwork and steel centering, compaction by vibrator, finishing uneven and honeycombed surface with C.M.-1:3 of sufficient minimum thickness to give a smooth and even surface, or roughening the surface if special finish is to be provided, curing and bailing out water. The C.M. 1:3 plaster is considered for rendering uneven and honeycombed surface only.( Excluding reinforcement, including cover block.) Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc.( Wooden centering / formwork will not be allowed.) With contractors own material, including all leads &amp; lifts etc. complete. C.C.-M-15 (40 MSA) including royalty charges.</p>

<p><b>Item No.8:-</b> Providing and laying in situ C.C. of required grade of trap / granite / quartzite / gneiss metal in foundation including necessary bailing out water, including plywood/steel form work, steel centering and excluding dewatering by pump compaction by vibrating finishing uneven and honeycombed surface with C.M.1:3 of sufficient minimum thickness to give a smooth and even surface or roughening the surface if special finish is to be provided, curing etc. complete.(Excluding reinforcement, including cover block) The C.M. 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering/formwork will not be allowed) With contractors own material, including all leads &amp; lifts etc. complete.C.C.M-15GRADE-40 M.S.A.</p>	<p><b>Item No.8:-</b> Providing and laying in situ C.C. of required grade of trap / granite / quartzite / gneiss metal in foundation including necessary bailing out water, including plywood/steel form work, steel centering and excluding dewatering by pump compaction by vibrating finishing uneven and honeycombed surface with C.M.1:3 of sufficient minimum thickness to give a smooth and even surface or roughening the surface if special finish is to be provided, curing etc. complete.(Excluding reinforcement, including cover block) The C.M. 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering/formwork will not be allowed) With contractors own material, including all leads &amp; lifts etc. complete.C.C.M-15GRADE-40 M.S.A. including royalty charges.</p>
<p><b>Item No.9:-</b>Providing and casting in situ cement concrete of required grade of trap / quartzite /granite /gneiss metal for R.C.C. Waist slab, and steps of staircases as per detailed design and drawings or as directed including steel centering, plywood/ steel formwork, steel props, compaction, finishing uneven and honeycombed surface with C.M. 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening the surface if special finish is to be provided and curing etc. complete. (Excluding einforcement, including cover block) The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. (Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc.) (Wooden centering will not be allowed) including all leads &amp; lifts etc. complete. C.C. M-20 GRADE)- 20 M.S.A.</p>	<p><b>Item No.9:-</b>Providing and casting in situ cement concrete of required grade of trap / quartzite /granite /gneiss metal for R.C.C. Waist slab, and steps of staircases as per detailed design and drawings or as directed including steel centering, plywood/ steel formwork, steel props, compaction, finishing uneven and honeycombed surface with C.M. 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening the surface if special finish is to be provided and curing etc. complete. (Excluding einforcement, including cover block) The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. (Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc.) (Wooden centering will not be allowed) including all leads &amp; lifts etc. complete. C.C. M-20 GRADE)- 20 M.S.A. with contractor own material including royalty charges.</p>
<p><b>Item No.11:-</b>Providing and laying cement concrete pipe of I.S. N.P. class of</p>	<p><b>Item No.11:-</b>Providing and laying cement concrete pipe of I.S. N.P. class of</p>

required diameter in proper line, level and slope including providing, fixing collars or spigot and socket joint by rubber ring and in C.M.1:2, including all leads & lifts etc. complete ( NP-3 Class 1200 mm C.C. Pipe	required diameter in proper line, level and slope including providing, fixing collars or spigot and socket joint by rubber ring and in C.M.1:2, including all leads & lifts etc. complete ( NP-3 Class 1200 mm C.C. Pipe) <b>with contractor own material.</b>
<b>Item No.12:-</b> Providing selected murum ( having P I < 6 ) Filling including laying in layers of 15cm to 20cm, watering and compaction With contractor's own materials, including all leads & lifts etc. complete	<b>Item No.12:-</b> Providing selected murum ( having P I < 6 ) Filling including laying in layers of 15cm to 20cm, watering and compaction With contractor's own materials, including all leads & lifts etc. complete <b>including royalty charges.</b>
<b>Item No. 14:-</b> Providing dry rubble stone pitching 23 cm (about 9" ) thick including all material, labour With contractor's own materials, including all leads & lifts etc. complete..	<b>Item No. 14:-</b> Providing dry rubble stone pitching 23 cm (about 9" ) thick including all material, labour With contractor's own materials, including all leads & lifts etc. complete. <b>including royalty charges.</b>
<b>Item No.15:-</b> Providing, Laying, Spreading and compacting stone aggregates of specific sizes to Water Bound Macadam specification including spreading in uniform thickness, hand packing, rolling with 3-wheeled steel/vibratory roller 8 to 10 tones in stages to proper grade and camber, applying and brooming requisite type of screening/binding material to fill up the interstices of coarse aggregate, watering and compacting to the required density, With contractor's own materials, including all leads & lifts etc. complete. lead and lift and as directed by Engineer in charge etc	<b>Item No.15:-</b> Providing, Laying, Spreading and compacting stone aggregates of specific sizes to Water Bound Macadam specification including spreading in uniform thickness, hand packing, rolling with 3-wheeled steel/vibratory roller 8 to 10 tones in stages to proper grade and camber, applying and brooming requisite type of screening/binding material to fill up the interstices of coarse aggregate, watering and compacting to the required density, With contractor's own materials, including all leads & lifts etc. complete. lead and lift and as directed by Engineer in charge etc <b>complete including royalty charges.</b>

#### Schedule "C"

Old	New
<b>Item No.3:-</b> Providing soling using 80 mm size / granite / quartzite / gneiss / trap metal in 15cm layer, including hand packing, filling voids with sand / grit,ramming,watering With contractors own material, including all leads & lifts etc. complete	<b>Item No.3:-</b> Providing soling using 80 mm size / granite / quartzite / gneiss / trap metal in 15cm layer, including hand packing, filling voids with sand / grit,ramming,watering With contractors own material, including all leads & lifts etc. complete <b>including royalty charges.</b>
<b>Item No.4-</b> Providing and filling sand below raft and in box return including compaction. As directed by Engineer in-	<b>Item No.4-</b> Providing and filling sand below raft and in box return including compaction. As directed by Engineer in-

<p>charge. With contractors own material, Including all leads &amp; lifts etc. complete.</p>	<p>charge. With contractors own material, Including all leads &amp; lifts etc. complete. <b>including royalty charges.</b></p>
<p><b>Item No.5:-</b>Providing and laying in situ M-10 / 1:3:6 cement concrete of trap / granite / quartzite / gneiss metal for leveling course below R.C.C. Raft and foundation, including necessary plywood / steel formwork and steel centering, compaction by vibrator, finishing curing etc, complete. The C.M.1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc.( Wooden centering / formwork will not be allowed.) With contractors own material, including all leads &amp; lifts etc, complete. rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bags, plastic, tarpaulin etc.( wooden centering / formwork will not be allowed.) with all lead and lift and as directed by Engineer in charge etc complete M-10 ( 40 MSA)</p>	<p><b>Item No.5:-</b>Providing and laying in situ M-10 / 1:3:6 cement concrete of trap / granite / quartzite / gneiss metal for leveling course below R.C.C. Raft and foundation, including necessary plywood / steel formwork and steel centering, compaction by vibrator, finishing curing etc, complete. The C.M.1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc.( Wooden centering / formwork will not be allowed.) With contractors own material, including all leads &amp; lifts etc, complete. rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bags, plastic, tarpaulin etc.( wooden centering / formwork will not be allowed.) with all lead and lift and as directed by Engineer in charge etc complete M-10 ( 40 MSA) <b>with contractor own material including royalty charges.</b></p>
<p><b>Item No.6:-</b>Providing and laying in situ c.c. of required grade of trap / granite / quartzite / gneiss metal for cut-off and curtain wall, including plywood / steel formwork and steel centering, compaction by vibrator, finishing uneven and honeycombed surface with C.M.-1:3 of sufficient minimum thickness to give a smooth and even surface or roughening the surface if special finish is to be provided, curing etc. complete.( Excluding reinforcement, including cover block.) The C.M.-1:3 plaster is considered for rendering uneven and honeycombed surface only.( Excluding cost of reinforcement ) Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc.( Wooden centering / formwork will not be allowed.) With contractors own material, including all leads &amp; lifts etc. complete.. C.C.-M-15 (20 MSA)</p>	<p><b>Item No.6:-</b>Providing and laying in situ c.c. of required grade of trap / granite / quartzite / gneiss metal for cut-off and curtain wall, including plywood / steel formwork and steel centering, compaction by vibrator, finishing uneven and honeycombed surface with C.M.-1:3 of sufficient minimum thickness to give a smooth and even surface or roughening the surface if special finish is to be provided, curing etc. complete.( Excluding reinforcement, including cover block.) The C.M.-1:3 plaster is considered for rendering uneven and honeycombed surface only.( Excluding cost of reinforcement ) Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc.( Wooden centering / formwork will not be allowed.) With contractors own material, including all leads &amp; lifts etc. complete.. C.C.-M-15 (20 MSA) <b>including royalty charges.</b></p>

**Item No.7:-**Providing and laying cement concrete of required grade of trap / granite / quartzite / gneiss metal for cast in situ piers, abutments, returns wings, Face wall etc. including provision of "V" shaped false joints to form suitable panels on the faces to approved design, including plywood / steel formwork and steel centering, compaction by vibrator, finishing uneven and honeycombed surface with C.M.-1:3 of sufficient minimum thickness to give a smooth and even surface, or roughening the surface if special finish is to be provided, curing and bailing out water. The C.M. 1:3 plaster is considered for rendering uneven and honeycombed surface only.( Excluding reinforcement, including cover block.) Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc.( Wooden centering / formwork will not be allowed.) With contractors own material, including all leads & lifts etc. complete.

C.C.-M-15 (40 MSA)

**Item No.7:-**Providing and laying cement concrete of required grade of trap / granite / quartzite / gneiss metal for cast in situ piers, abutments, returns wings, Face wall etc. including provision of "V" shaped false joints to form suitable panels on the faces to approved design, including plywood / steel formwork and steel centering, compaction by vibrator, finishing uneven and honeycombed surface with C.M.-1:3 of sufficient minimum thickness to give a smooth and even surface, or roughening the surface if special finish is to be provided, curing and bailing out water. The C.M. 1:3 plaster is considered for rendering uneven and honeycombed surface only.( Excluding reinforcement, including cover block.) Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc.( Wooden centering / formwork will not be allowed.) With contractors own material, including all leads & lifts etc. complete.

C.C.-M-15 (40 MSA) including royalty charges.

<p><b>Item No.8:-</b> Providing and laying in situ C.C. of required grade of trap / granite / quartzite / gneiss metal in foundation including necessary bailing out water, including plywood/steel form work, steel centering and excluding dewatering by pump compaction by vibrating finishing uneven and honeycombed surface with C.M.1:3 of sufficient minimum thickness to give a smooth and even surface or roughening the surface if special finish is to be provided, curing etc. complete.(Excluding reinforcement, including cover block) The C.M. 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering/formwork will not be allowed) With contractors own material, including all leads &amp; lifts etc. complete.C.C.M-15GRADE-40 M.S.A.</p>	<p><b>Item No.8:-</b> Providing and laying in situ C.C. of required grade of trap / granite / quartzite / gneiss metal in foundation including necessary bailing out water, including plywood/steel form work, steel centering and excluding dewatering by pump compaction by vibrating finishing uneven and honeycombed surface with C.M.1:3 of sufficient minimum thickness to give a smooth and even surface or roughening the surface if special finish is to be provided, curing etc. complete.(Excluding reinforcement, including cover block) The C.M. 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering/formwork will not be allowed) With contractors own material, including all leads &amp; lifts etc. complete.C.C.M-15GRADE-40 M.S.A. including royalty charges.</p>
<p><b>Item No.9:-</b>Providing and casting in situ cement concrete of required grade of trap / quartzite /granite /gneiss metal for R.C.C. Waist slab, and steps of staircases as per detailed design and drawings or as directed including steel centering, plywood/ steel formwork, steel props, compaction, finishing uneven and honeycombed surface with C.M. 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening the surface if special finish is to be provided and curing etc. complete. (Excluding einforcement, including cover block) The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. (Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc.) (Wooden centering will not be allowed) including all leads &amp; lifts etc. complete. C.C. M-20 GRADE)- 20 M.S.A.</p>	<p><b>Item No.9:-</b>Providing and casting in situ cement concrete of required grade of trap / quartzite /granite /gneiss metal for R.C.C. Waist slab, and steps of staircases as per detailed design and drawings or as directed including steel centering, plywood/ steel formwork, steel props, compaction, finishing uneven and honeycombed surface with C.M. 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening the surface if special finish is to be provided and curing etc. complete. (Excluding einforcement, including cover block) The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. (Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc.) (Wooden centering will not be allowed) including all leads &amp; lifts etc. complete. C.C. M-20 GRADE)- 20 M.S.A. with contractor own material including royalty charges.</p>
<p><b>Item No.11:-</b>Providing and laying cement concrete pipe of I.S. N.P. class of</p>	<p><b>Item No.11:-</b>Providing and laying cement concrete pipe of I.S. N.P. class of</p>

required diameter in proper line, level and slope including providing, fixing collars or spigot and socket joint by rubber ring and in C.M.1:2, including all leads & lifts etc. complete ( NP-3 Class 1200 mm C.C. Pipe	required diameter in proper line, level and slope including providing, fixing collars or spigot and socket joint by rubber ring and in C.M.1:2, including all leads & lifts etc. complete ( NP-3 Class 1200 mm C.C. Pipe) <b>with contractor own material.</b>
<b>Item No.12:-</b> Providing selected murum ( having P I < 6 ) Filling including laying in layers of 15cm to 20cm, watering and compaction With contractor's own materials, including all leads & lifts etc. complete	<b>Item No.12:-</b> Providing selected murum ( having P I < 6 ) Filling including laying in layers of 15cm to 20cm, watering and compaction With contractor's own materials, including all leads & lifts etc. complete <b>including royalty charges.</b>
<b>Item No. 14:-</b> Providing dry rubble stone pitching 23 cm (about 9" ) thick including all material, labour With contractor's own materials, including all leads & lifts etc. complete..	<b>Item No. 14:-</b> Providing dry rubble stone pitching 23 cm (about 9" ) thick including all material, labour With contractor's own materials, including all leads & lifts etc. complete. <b>including royalty charges.</b>
<b>Item No.15:-</b> Providing, Laying, Spreading and compacting stone aggregates of specific sizes to Water Bound Macadam specification including spreading in uniform thickness, hand packing, rolling with 3-wheeled steel/vibratory roller 8 to 10 tones in stages to proper grade and camber, applying and brooming requisite type of screening/binding material to fill up the interstices of coarse aggregate, watering and compacting to the required density, With contractor's own materials, including all leads & lifts etc. complete. lead and lift and as directed by Engineer in charge etc	<b>Item No.15:-</b> Providing, Laying, Spreading and compacting stone aggregates of specific sizes to Water Bound Macadam specification including spreading in uniform thickness, hand packing, rolling with 3-wheeled steel/vibratory roller 8 to 10 tones in stages to proper grade and camber, applying and brooming requisite type of screening/binding material to fill up the interstices of coarse aggregate, watering and compacting to the required density, With contractor's own materials, including all leads & lifts etc. complete. lead and lift and as directed by Engineer in charge etc <b>complete including royalty charges.</b>

Executive Engineer  
Gosikhurd Right Bank Canal Division  
No. 1 Wahi ( Pauni)